



## I-680 HOV LANES (NORTH MAIN STREET TO MARINA VISTA)

**PROPONENT:  
CALTRANS**

**PROJECT NO:  
1116C**

### DESCRIPTION:

This project provided new HOV lanes on I-680 in the northbound direction from State Route (SR) 242 in Concord to the Marina Vista Interchange in Martinez and in the southbound direction from the Marina Vista Interchange in Martinez to North Main Street in Walnut Creek. The project also provided a collector-distributor road system on I-680 for movements to and from SR 4 at the I-680/SR 4 Interchange.

This project was accomplished by minor widening of the right hand shoulders and re-striping of the existing I-680 lanes to a combination of 11-foot and 12-foot wide lanes. Several structures required widening.

### STATUS:

The CEQA/NEPA environmental clearance was obtained in December 1999. Final design by Caltrans was completed March 2003. Construction started March 2003 and was substantially completed in April 2005.

FUNDING SOURCES	(\$ X 1000):
Federal	4,390.0
STIP	47,230.0
SHOPP	13,228.0
Measure C (Esc.\$) <sup>1</sup>	<u>2,152.0</u>
<b>TOTAL</b>	<b>\$ 67,000.0</b>

<sup>1</sup> Measure C funds shown in escalated dollars. Actual commitment is in 1988 dollars as shown in Appendix A.